

# LMH6639 190MHz Rail-to-Rail Output Amplifier with Disable

Check for Samples: LMH6639

### **FEATURES**

- (V<sub>S</sub> = 5V, Typical Values Unless Specified)
- Supply Current (No Load) 3.6mA
- Supply Current (Off Mode) 400µA
- Output Resistance (Closed Loop 1MHz) 0.186Ω
- $-3dB BW (A_V = 1) 190MHz$
- Settling Time 33nsec
- Input Common Mode Voltage -0.2V to 4V
- Output Voltage Swing 40mV from Rails
- Linear Output Current 110mA
- Total Harmonic Distortion –60dBc
- Fully Characterized for 3V, 5V and ±5V
- No Output Phase Reversal with CMVR Exceeded
- Excellent Overdrive Recovery
- Off Isolation 1MHz -70dB
- Differential Gain 0.12%
- Differential Phase 0.045°

### **APPLICATIONS**

- Active Filters
- CD/DVD ROM
- ADC Buffer Amplifier
- Portable Video
- Current Sense Buffer

### DESCRIPTION

The LMH6639 is a voltage feedback operational amplifier with a rail-to-rail output drive capability of 110mA. Employing Tl's patented VIP10 process, the LMH6639 delivers a bandwidth of 190MHz at a current consumption of only 3.6mA. An input common mode voltage range extending to 0.2V below the V and to within 1V of V<sup>+</sup>, makes the LMH6639 a true single supply op-amp. The output voltage range extends to within 30mV of either supply rail providing the user with a dynamic range that is especially desirable in low voltage applications.

The LMH6639 offers a slew rate of 172V/µs resulting in a full power bandwidth of approximately 28MHz. The LMH6639 also offers protection for the input transistors by using two anti-parallel diodes and a series resistor connected across the inputs. The Ton value of 83nsec combined with a settling time of 33nsec makes this device ideally suited for multiplexing applications (see application note for details). Careful attention has been paid to ensure device stability under all operating voltages and modes. The result is a very well behaved frequency response characteristic for any gain setting including +1, and excellent specifications for driving video cables including harmonic distortion of -60dBc, differential gain of 0.12% and differential phase of 0.045°




Figure 1. Typical Single Supply Schematic

Please be aware that an important notice concerning availability, standard warranty, and use in critical applications of Texas Instruments semiconductor products and disclaimers thereto appears at the end of this data sheet.

All trademarks are the property of their respective owners.





These devices have limited built-in ESD protection. The leads should be shorted together or the device placed in conductive foam during storage or handling to prevent electrostatic damage to the MOS gates.

Absolute Maximum Ratings (1)(2)

ESD Tolerance	-	2KV <sup>(3)</sup>
		200V <sup>(4)</sup>
V <sub>IN</sub> Differential		±2.5V
Input Current	±10mA	
Supply Voltage (V <sup>+</sup> – V <sup>-</sup> )	13.5V	
Voltage at Input/Output pins		V <sup>+</sup> +0.8V, V <sup>−</sup> −0.8V
Storage Temperature Range		−65°C to +150°C
Junction Temperature <sup>(5)(6)</sup>		+150°C
Soldering Information	Infrared or Convection (20 sec)	235°C
	Wave Soldering (10 sec)	260°C

- (1) Absolute Maximum Ratings indicate limits beyond which damage to the device may occur. Operating Ratings indicate conditions for which the device is intended to be functional, but specific performance is not ensured. For ensured specifications and the test conditions, see the Electrical Characteristics.
- (2) If Military/Aerospace specified devices are required, please contact the Texas Instruments Sales Office/ Distributors for availability and specifications.
- (3) Human body model,  $1.5k\Omega$  in series with 100pF.
- (4) Machine Model, 0Ω in series with 200pF.
- (5) The maximum power dissipation is a function of T<sub>J(MAX)</sub>, θ<sub>JA</sub>, and T<sub>A</sub>. The maximum allowable power dissipation at any ambient temperature is P<sub>D</sub> = (T<sub>J(MAX)</sub> T<sub>A</sub>)/ θ<sub>JA</sub>. All numbers apply for packages soldered directly onto a PC board.
- (6) Applies to both single-supply and split-supply operation. Continuous short circuit operation at elevated ambient temperature can result in exceeding the maximum allowed junction temperature of 150°C.

# Operating Ratings<sup>(1)</sup>

Supply Voltage (V <sup>+</sup> to V <sup>-</sup> )		3V to 12V
Operating Temperature Range <sup>(2)</sup>	-40°C to +85°C	
Package Thermal Resistance (θ <sub>JA</sub> ) <sup>(2)</sup>	SOT-23-6	265°C/W
	SOIC-8	190°C/W

- (1) Absolute Maximum Ratings indicate limits beyond which damage to the device may occur. Operating Ratings indicate conditions for which the device is intended to be functional, but specific performance is not ensured. For ensured specifications and the test conditions, see the Electrical Characteristics.
- (2) The maximum power dissipation is a function of  $T_{J(MAX)}$ ,  $\theta_{JA}$ , and  $T_A$ . The maximum allowable power dissipation at any ambient temperature is  $P_D = (T_{J(MAX)} T_A)/\theta_{JA}$ . All numbers apply for packages soldered directly onto a PC board.

### **3V Electrical Characteristics**

Unless otherwise specified, all limits ensured for at  $T_J = 25^{\circ}C$ ,  $V^+ = 3V$ ,  $V^- = 0V$ ,  $V_O = V_{CM} = V^+/2$ , and  $R_L = 2k\Omega$  to  $V^+/2$ . **Boldface** limits apply at the temperature extremes.

Symbol	Parameter	Con	ditions	Min <sup>(1)</sup>	Typ <sup>(2)</sup>	Max <sup>(1)</sup>	Units	
BW	-3dB BW	A <sub>V</sub> = +1	A <sub>V</sub> = +1				NAL I—	
		A <sub>V</sub> = −1			63		MHz	
BW <sub>0.1dB</sub>	0.1dB Gain Flatness	$R_F = 2.65k\Omega$ , $R_L =$	1kΩ,		16.4		MHz	
FPBW	Full Power Bandwidth	$A_V = +1, V_{OUT} = 2V$ $V^+ = 1.8V, V^- = 1.2$	′ <sub>PP</sub> , −1dB V		21		MHz	
GBW	Gain Bandwidth product	A <sub>V</sub> = +1			83		MHz	
e <sub>n</sub>	Input-Referred Voltage Noise	$R_F = 33k\Omega$	f = 10kHz		19		nV/√ <del>Hz</del>	
			f = 1MHz		16		IIV/VHZ	
in	Input-Referred Current Noise	$R_F = 1M\Omega$	f = 10kHz		1.30		- A / /II	
			f = 1MHz				pA/√Hz	
THD	Total Harmonic Distortion	$f = 5MHz$ , $V_O = 2V_F$ $R_L = 1k\Omega$ to $V^+/2$		-50		dBc		

- All limits are ensured by testing or statistical analysis.
- (2) Typical values represent the most likely parametric norm.



## **3V Electrical Characteristics (continued)**

Unless otherwise specified, all limits ensured for at  $T_J = 25^{\circ}C$ ,  $V^+ = 3V$ ,  $V^- = 0V$ ,  $V_O = V_{CM} = V^+/2$ , and  $R_L = 2k\Omega$  to  $V^+/2$ . **Boldface** limits apply at the temperature extremes.

Symbol	Parameter	Conditions	Min <sup>(1)</sup>	Typ <sup>(2)</sup>	Max <sup>(1)</sup>	Units	
T <sub>S</sub>	Settling Time	$V_O = 2V_{PP}, \pm 0.1\%$		37		ns	
SR	Slew Rate	$A_V = -1^{(3)}$	120	167		V/µs	
V <sub>OS</sub>	Input Offset Voltage			1.01	5 <b>7</b>	mV	
TC V <sub>OS</sub>	Input Offset Average Drift	See <sup>(4)</sup>		8		μV/°C	
I <sub>B</sub>	Input Bias Current	See <sup>(5)</sup>		-1.02	-2.6 <b>-3.5</b>	μΑ	
I <sub>OS</sub>	Input Offset Current			20	800 <b>1000</b>	nA	
R <sub>IN</sub>	Common Mode Input Resistance	$A_V = +1$ , $f = 1kHz$ , $R_S = 1M\Omega$		6.1		ΜΩ	
C <sub>IN</sub>	Common Mode Input Capacitance	$A_V = +1, R_S = 100k\Omega$		1.35		pF	
CMVR	Input Common-Mode Voltage Range			-0.3	-0.2 - <b>0.1</b>	V	
			1.8 <b>1.6</b>	2		V	
CMRR	Common Mode Rejection Ratio	See <sup>(6)</sup>	72	93		dB	
A <sub>VOL</sub>	Large Signal Voltage Gain	$V_O = 2V_{PP}$ , $R_L = 2k\Omega$ to $V^+/2$	80 <b>76</b>	100		dB	
		$V_0 = 2V_{PP}, R_L = 150\Omega \text{ to } V^{+}/2$	74 <b>70</b>	78		ив	
$V_{O}$	Output Swing	$R_L = 2k\Omega$ to V <sup>+</sup> /2, $V_{ID} = 200$ mV	2.90	2.98			
	High	$R_L = 150\Omega$ to V <sup>+</sup> /2, $V_{ID} = 200$ mV	2.75	2.93		V	
		$R_L = 50\Omega$ to V <sup>+</sup> /2, $V_{ID} = 200$ mV	2.6	2.85			
	Output Swing	$R_L = 2k\Omega \text{ to V}^+/2, V_{ID} = -200\text{mV}$ 25		25	75		
	Low	$R_L = 150\Omega$ to V <sup>+</sup> /2, $V_{ID} = -200$ mV		75	200	mV	
		$R_L = 50\Omega$ to V <sup>+</sup> /2, $V_{ID} = -200$ mV		130	300		
I <sub>SC</sub>	Output Short Circuit Current	Sourcing to V <sup>+</sup> /2 <sup>(7)</sup>	50 <b>35</b>	120		^	
		Sinking to V <sup>+</sup> /2 <sup>(7)</sup>	67 <b>40</b>	140		mA	
I <sub>OUT</sub>	Output Current	V <sub>O</sub> = 0.5V from either supply		99		mA	
PSRR	Power Supply Rejection Ratio	See <sup>(6)</sup>	72	96		dB	
I <sub>S</sub>	Supply Current (Enabled)	No Load		3.5	5.6 <b>7.5</b>	^	
	Supply Current (Disabled)			0.3	0.5 <b>0.7</b>	mA	
TH_SD	Threshold Voltage for Shutdown Mode			V <sup>+</sup> -1.59		V	
I_SD PIN	Shutdown Pin Input Current	SD Pin Connect to 0V <sup>(8)</sup>		-13		μΑ	
T <sub>ON</sub>	On Time After Shutdown			83		nsec	
T <sub>OFF</sub>	Off Time to Shutdown			160		nsec	
R <sub>OUT</sub>	Output Resistance Closed Loop	$R_F = 10k\Omega$ , $f = 1kHz$ , $A_V = -1$		27	_	m0	
		$R_F = 10k\Omega$ , $f = 1MHz$ , $A_V = -1$		266		mΩ	

- (3) Slew rate is the average of the rising and falling slew rates.
- (4) Offset voltage average drift determined by dividing the change in V<sub>OS</sub> at temperature extremes into the total temperature change.
- (5) Positive current corresponds to current flowing into the device.
- (6) f ≤ 1kHz (see typical performance Characteristics)
- (7) Short circuit test is a momentary test.
- (8) Positive current corresponds to current flowing into the device.



### **5V Electrical Characteristics**

Unless otherwise specified, all limits ensured for at  $T_J = 25^{\circ}C$ ,  $V^+ = 5V$ ,  $V^- = 0V$ ,  $V_O = V_{CM} = V^+/2$ , and  $R_L = 2k\Omega$  to  $V^+/2$ . **Boldface** limits apply at the temperature extremes.

Symbol	Parameter	Condition	Min <sup>(1)</sup>	Typ <sup>(2)</sup>	Max <sup>(1)</sup>	Units	
BW	-3dB BW	A <sub>V</sub> = +1		130	190		N 41 1
		A <sub>V</sub> = −1			64		MHz
BW <sub>0.1dB</sub>	0.1dB Gain Flatness	$R_F = 2.51k\Omega$ , $R_L = 1k\Omega$ ,			16.4		MHz
FPBW	Full Power Bandwidth	$A_V = +1, V_{OUT} = 2V_{PP}, -$	1dB		28		MHz
GBW	Gain Bandwidth Product	A <sub>V</sub> = +1			86		MHz
e <sub>n</sub>	Input-Referred Voltage Noise	$R_F = 33k\Omega$	f = 10kHz		19		nV/√Hz
			f = 1MHz		16		NV/VHZ
i <sub>n</sub>	Input-Referred Current Noise	$R_F = 1M\Omega$	f = 10KHz		1.35		5 A /a/Ll=
			f = 1MHz		0.35		pA/√Hz
THD	Total Harmonic Distortion	$f = 5MHz$ , $V_O = 2V_{PP}$ , $A_V$ $R_L = 1k\Omega$ to $V^+/2$	<sub>/</sub> = +2		-60		dBc
DG	Differential Gain	NTSC, $A_V = +2$ $R_L = 150\Omega$ to $V^+/2$			0.12		%
DP	Differential Phase	NTSC, $A_V = +2$ $R_L = 150\Omega$ to $V^+/2$			0.045		deg
T <sub>S</sub>	Settling Time	$V_O = 2V_{PP}, \pm 0.1\%$			33		ns
SR	Slew Rate	$A_V = -1^{(3)}$		130	172		V/µs
Vos	Input Offset Voltage				1.02	5 <b>7</b>	mV
TC V <sub>OS</sub>	Input Offset Average Drift	See <sup>(4)</sup>			8		μV/°C
I <sub>B</sub>	Input Bias Current	See <sup>(5)</sup>			-1.2	-2.6 <b>-3.25</b>	μA
I <sub>OS</sub>	Input Offset Current				20	800 <b>1000</b>	nA
R <sub>IN</sub>	Common Mode Input Resistance	$A_V = +1$ , $f = 1kHz$ , $R_S =$	1ΜΩ		6.88		МΩ
C <sub>IN</sub>	Common Mode Input Capacitance	$A_V = +1, R_S = 100k\Omega$			1.32		pF
CMVR	Common-Mode Input Voltage Range	CMRR ≥ 50dB		-0.3	-0.2 <b>-0.1</b>	V	
				4	3.8 <b>3.6</b>		
CMRR	Common Mode Rejection Ratio	See <sup>(6)</sup>		72	95		dB
A <sub>VOL</sub>	Large Signal Voltage Gain	$V_O = 4V_{PP}$ $R_L = 2k\Omega$ to V <sup>+</sup> /2		86 <b>82</b>	100		dD
		$V_O = 3.75V_{PP}$ $R_L = 150\Omega \text{ to V}^+/2$		74 <b>70</b>	77		- dB
Vo	Output Swing	$R_L = 2k\Omega$ to $V^+/2$ , $V_{ID} = 2$	4.90	4.97			
	High	$R_L = 150\Omega$ to V <sup>+</sup> /2, $V_{ID} =$	4.65	4.90		V	
		$R_L = 50\Omega$ to V <sup>+</sup> /2, $V_{ID} = 3$	4.40	4.77			
	Output Swing	$R_L = 2k\Omega$ to $V^+/2$ , $V_{ID} = -$		25	100		
	Low	$R_L = 150\Omega$ to $V^+/2$ , $V_{ID} =$	= -200mV		85	200	mV
		$R_L = 50\Omega$ to V <sup>+</sup> /2, $V_{ID} = 10$	-200mV		190	400	

Product Folder Links: LMH6639

<sup>(1)</sup> All limits are ensured by testing or statistical analysis.(2) Typical values represent the most likely parametric norm.

Slew rate is the average of the rising and falling slew rates.

Offset voltage average drift determined by dividing the change in VOS at temperature extremes into the total temperature change.

Positive current corresponds to current flowing into the device.

f ≤ 1kHz (see typical performance Characteristics) (6)



### **5V Electrical Characteristics (continued)**

Unless otherwise specified, all limits ensured for at  $T_J = 25^{\circ}C$ ,  $V^+ = 5V$ ,  $V^- = 0V$ ,  $V_O = V_{CM} = V^+/2$ , and  $R_L = 2k\Omega$  to  $V^+/2$ . Boldface limits apply at the temperature extremes.

Symbol	Parameter	Conditions	Min <sup>(1)</sup>	Typ <sup>(2)</sup>	Max <sup>(1)</sup>	Units
I <sub>SC</sub>	Output Short Circuit Current	Sourcing to V <sup>+</sup> /2 <sup>(7)</sup>	100 <b>79</b>	160		
		Sinking from V <sup>+</sup> /2 <sup>(7)</sup>	120 <b>85</b>	190		mA
I <sub>OUT</sub>	Output Current	V <sub>O</sub> = 0.5V from either supply		110		mA
PSRR	Power Supply Rejection Ratio	See <sup>(6)</sup>	72	96		dB
I <sub>S</sub>	Supply Current (Enabled)	No Load		3.6	5.8 <b>8.0</b>	A
	Supply Current (Disabled)			0.40	0.8 <b>1.0</b>	mA
TH_SD	Threshold Voltage for Shutdown Mode			V <sup>+</sup> −1.65		V
I_SD PIN	Shutdown Pin Input Current	SD Pin Connected to 0V <sup>(5)</sup>		-30		μΑ
T <sub>ON</sub>	On Time after Shutdown			83		nsec
T <sub>OFF</sub>	Off Time to Shutdown			160		nsec
R <sub>OUT</sub>	Output Resistance Closed Loop	$R_F = 10k\Omega$ , $f = 1kHz$ , $A_V = -1$		29		C
		$R_F = 10k\Omega$ , $f = 1MHz$ , $A_V = -1$		253		mΩ

<sup>(7)</sup> Short circuit test is a momentary test.

### ±5V Electrical Characteristics

Unless otherwise specified, all limits ensured for at  $T_J$  = 25°C,  $V_{SUPPLY}$  = ±5V,  $V_O$  =  $V_{CM}$  = GND, and  $R_L$  = 2k $\Omega$  to V<sup>+</sup>/2. **Boldface** limits apply at the temperature extremes.

Symbol	Parameter	Cond	litions	Min <sup>(1)</sup>	Typ <sup>(2)</sup>	Max <sup>(1)</sup>	Units
BW	-3dB BW	A <sub>V</sub> = +1		150	228		N41.1-
		A <sub>V</sub> = −1			65		MHz
BW <sub>0.1dB</sub>	0.1dB Gain Flatness	$R_F = 2.26k\Omega, R_L = 1$	kΩ		18		MHz
FPBW	Full Power Bandwidth	$A_V = +1$ , $V_{OUT} = 2V_F$	<sub>PP</sub> , −1dB		29		MHz
GBW	Gain Bandwidth Product	A <sub>V</sub> = +1			90		MHz
e <sub>n</sub>	Input-Referred Voltage Noise	$R_F = 33k\Omega$	f = 10kHz		19		->///
		f = 1MHz			16		nV/√Hz
in	Input-Referred Current Noise	Referred Current Noise $R_F = 1M\Omega$			1.13		pA/√ <del>Hz</del>
				0.34			
THD	Total Harmonic Distortion	$f = 5MHz, V_O = 2V_{Pl}$ $R_L = 1k\Omega$	P, A <sub>V</sub> = +2,		-71.2		dBc
DG	Differential Gain	NTSC, $A_V = +2$ $R_L = 150\Omega$			0.11		%
DP	Differential Phase	NTSC, $A_V = +2$ $R_L = 150\Omega$			0.053		deg
T <sub>S</sub>	Settling Time	$V_O = 2V_{PP}, \pm 0.1\%$			33		ns
SR	Slew Rate	$A_V = -1^{(3)}$		140	200		V/µs
V <sub>OS</sub>	Input Offset Voltage				1.03	5 <b>7</b>	mV
TC V <sub>OS</sub>	Input Offset Voltage Drift	See <sup>(4)</sup>			8		μV/°C
I <sub>B</sub>	Input Bias Current	See <sup>(5)</sup>			-1.40	-2.6 <b>-3.25</b>	μA

All limits are ensured by testing or statistical analysis.

Typical values represent the most likely parametric norm. Slew rate is the average of the rising and falling slew rates.

Offset voltage average drift determined by dividing the change in VOS at temperature extremes into the total temperature change.

Positive current corresponds to current flowing into the device.



## ±5V Electrical Characteristics (continued)

Unless otherwise specified, all limits ensured for at  $T_J = 25^{\circ}\text{C}$ ,  $V_{\text{SUPPLY}} = \pm 5\text{V}$ ,  $V_O = V_{\text{CM}} = \text{GND}$ , and  $R_L = 2k\Omega$  to  $V^+/2$ . **Boldface** limits apply at the temperature extremes.

Symbol	Parameter	Conditions	Min <sup>(1)</sup>	Typ <sup>(2)</sup>	Max <sup>(1)</sup>	Units	
I <sub>OS</sub>	Input Offset Current			20	800 <b>1000</b>	nA	
R <sub>IN</sub>	Common Mode Input Resistance	$A_V$ +1, $f = 1kHz$ , $R_S = 1M\Omega$		7.5		ΜΩ	
C <sub>IN</sub>	Common Mode Input Capacitance	$A_V = +1, R_S = 100k\Omega$		1.28		pF	
CMVR	Common Mode Input Voltage Range	CMRR ≥ 50dB		-5.3	-5.2 <b>-5.1</b>	V	
			3.8 <b>3.6</b>	4.0		V	
CMRR	Common Mode Rejection Ratio	See <sup>(6)</sup>	72	95		dB	
A <sub>VOL</sub>	Large Signal Voltage Gain	$V_O = 9V_{PP}, R_L = 2k\Omega$	88 <b>84</b>	100		40	
		$V_O = 8V_{PP}, R_L = 150\Omega$	74 <b>70</b>	77		dB	
Vo	Output Swing	$R_L = 2k\Omega$ , $V_{ID} = 200mV$	4.85	4.96		V	
	High	$R_L = 150\Omega, V_{ID} = 200 \text{mV}$	4.55	4.80			
		$R_L = 50\Omega, V_{ID} = 200 \text{mV}$	3.60	4.55			
	Output Swing	$R_L = 2k\Omega$ , $V_{ID} = -200$ mV		-4.97 -4.90			
	Low	$R_{L} = 150\Omega, V_{ID} = -200 \text{mV}$		-4.85	-4.55	V	
		$R_L = 50\Omega$ , $V_{ID} = -200$ mV		-4.65	-4.30		
I <sub>SC</sub>	Output Short Circuit Current	Sourcing to Ground <sup>(7)</sup>	100 <b>80</b>	168		- mA	
		Sinking to Ground <sup>(7)</sup>	110 <b>85</b>	190			
I <sub>OUT</sub>	Output Current	V <sub>O</sub> = 0.5V from either supply		112		mA	
PSRR	Power Supply Rejection Ratio	See <sup>(8)</sup>	72	96		dB	
Is	Supply Current (Enabled)	No Load		4.18	6.5 <b>8.5</b>	m ^	
	Supply Current (Disabled)			0.758	1.0 <b>1.3</b>	– mA	
TH_SD	Threshold Voltage for Shutdown Mode			V <sup>+</sup> - 1.67		V	
I_SD PIN	Shutdown Pin Input Current	SD Pin Connected to -5V <sup>(9)</sup>		-84		μA	
T <sub>ON</sub>	On Time after Shutdown			83		nsec	
T <sub>OFF</sub>	Off Time to Shutdown			160		nsec	
R <sub>OUT</sub>	Output Resistance Closed Loop	$R_F = 10k\Omega$ , $f = 1kHz$ , $A_V = -1$		32		mO.	
		$R_F = 10k\Omega$ , $f = 1MHz$ , $A_V = -1$ 226				mΩ	

<sup>(6)</sup>  $f \le 1kHz$  (see typical performance Characteristics)

<sup>(7)</sup> Short circuit test is a momentary test.

<sup>(8)</sup> f ≤ 1kHz (see typical performance Characteristics)

<sup>(9)</sup> Positive current corresponds to current flowing into the device.



# **Connection Diagram**




Figure 2. SOT-23-6 Top View




Figure 3. SOIC-8 Top View



# **Typical Performance Characteristics**

At  $T_J = 25^{\circ}\text{C}$ ,  $V^+ = +2.5$ ,  $V^- = -2.5\text{V}$ ,  $R_F = 330\Omega$  for  $A_V = +2$ ,  $R_F = 1k\Omega$  for  $A_V = -1$ . Unless otherwise specified.

Product Folder Links: LMH6639

# Output Sinking Saturation Voltage vs. I<sub>OUT</sub> for Various Temperature




Figure 4.

# Positive Output Saturation Voltage vs. V<sub>SUPPLY</sub> for Various Temperature





Figure 6.



# Output Sourcing Saturation Voltage vs. I<sub>OUT</sub> for Various Temperature




Figure 5.

# Negative Output Saturation Voltage vs. V<sub>SUPPLY</sub> for Various Temperature




Figure 7.




Figure 9.



At  $T_J = 25^{\circ}C$ ,  $V^+ = +2.5$ ,  $V^- = -2.5V$ ,  $R_F = 330\Omega$  for  $A_V = +2$ ,  $R_F = 1k\Omega$  for  $A_V = -1$ . Unless otherwise specified.




Figure 10.





Figure 12.



V<sub>OS</sub> vs. V<sub>S</sub> for 3 Representative Units T<sub>J</sub> = 125℃ UNIT 1 0 UNIT 2 Vos (mV) -0.5 -1 UNİT 3 -1.5 -2 2 3 6 7 10 4 9 8 V<sub>S</sub> (V)

Figure 11.




Figure 13.




Figure 15.

Copyright © 2002–2013, Texas Instruments Incorporated



At  $T_J = 25^{\circ}C$ ,  $V^+ = +2.5$ ,  $V^- = -2.5V$ ,  $R_F = 330\Omega$  for  $A_V = +2$ ,  $R_F = 1k\Omega$  for  $A_V = -1$ . Unless otherwise specified.




Figure 16.





Figure 18.






Figure 17.







Figure 19.








At  $T_J = 25^{\circ}C$ ,  $V^+ = +2.5$ ,  $V^- = -2.5V$ ,  $R_F = 330\Omega$  for  $A_V = +2$ ,  $R_F = 1k\Omega$  for  $A_V = -1$ . Unless otherwise specified.

























Figure 27.



At  $T_J = 25^{\circ}C$ ,  $V^+ = +2.5$ ,  $V^- = -2.5V$ ,  $R_F = 330\Omega$  for  $A_V = +2$ ,  $R_F = 1k\Omega$  for  $A_V = -1$ . Unless otherwise specified.






Figure 28.



awar Cwaan



Slew Rate (Positive)

1.50

1.00

0.50

-0.50

-1.00

INPUT

-1.50

4 ns/DIV Figure 29.




Figure 31.





Figure 33.



At  $T_J = 25^{\circ}C$ ,  $V^+ = +2.5$ ,  $V^- = -2.5V$ ,  $R_F = 330\Omega$  for  $A_V = +2$ ,  $R_F = 1k\Omega$  for  $A_V = -1$ . Unless otherwise specified.









Figure 36.










Figure 39.



At  $T_J = 25^{\circ}C$ ,  $V^+ = +2.5$ ,  $V^- = -2.5V$ ,  $R_F = 330\Omega$  for  $A_V = +2$ ,  $R_F = 1k\Omega$  for  $A_V = -1$ . Unless otherwise specified.






Figure 40.

# $\begin{array}{c} R_L = 100\Omega \\ C_L = \sim 5 pF \end{array}$

Large Signal Pulse Response (R<sub>L</sub> = 2k)

 $\dot{V}_S = 3V$   $\dot{A}_V = +1$ 

Figure 41.

### Large Signal Pulse Response




Figure 42.

### Large Signal Pulse Response




Figure 43.



### **APPLICATION NOTES**

### INPUT AND OUTPUT TOPOLOGY

All input / output pins are protected against excessive voltages by ESD diodes connected to V+ and V- rails (see Figure 44). These diodes start conducting when the input / output pin voltage approaches 1V<sub>be</sub> beyond V+ or Vto protect against over voltage. These diodes are normally reverse biased. Further protection of the inputs is provided by the two resistors (R in Figure 44), in conjunction with the string of anti-parallel diodes connected between both bases of the input stage. The combination of these resistors and diodes reduces excessive differential input voltages approaching 2V<sub>be</sub>. The most common situation when this occurs is when the device is put in shutdown and the LMH6639's inputs no longer follow each other. In such a case, the diodes may conduct. As a consequence, input current increases, and a portion of signal may appear at the Hi-Z output. Another possible situation for the conduction of these diodes is when the LMH6639 is used as a comparator (or with little or no feedback). In either case, it is important to make sure that the subsequent current flow through the device input pins does not violate the Absolute Maximum Ratings of the device. To limit the current through the protection circuit extra series resistors can be placed. Together with the build in series resistors of several hundred ohms this extra resistors can limit the input current to a safe number depending on the used application. Be aware of the effect that extra series resistors may impact the switching speed of the device. A special situation occurs when the part is configured for a gain of +1, which means the output is directly connected to the inverting input, see Figure 45. When the part is now placed in shutdown mode the output comes in a high impedance state and is unable to keep the inverting input at the same level as the non-inverting input. In many applications the output is connected to the ground via a low impedance resistor. When this situation occurs and there is a DC voltage offset of more than 2 volt between the non-inverting input and the output, current flows from the non-inverting input through the series resistors R via the bypass diodes to the output. Now the input current becomes much bigger than expected and in many cases the source at the input cannot deliver this current and will drop down. Be sure in this situation that no DC current path is available from the non-inverting input to the output pin, or from the output pin to the load resistor. This DC path is drawn by a curved line and can be broken by placing one of the capacitors CIN or COUT or both, depending on the used application.




Figure 44.





Figure 45. DC path while in shutdown



### **MULTIPLEXING 5 AND 10MHz**

The LMH6639 may be used to implement a circuit which multiplexes two signals of different frequencies. Three LMH6639 high speed op-amps are used in the circuit of Figure 46 to accomplish the multiplexing function. Two LMH6639 are used to provide gain for the input signals, and the third device is used to provide output gain for the selected signal.



Note: Pin numbers pertain to SOIC-8 package

Figure 46. Multiplexer

Multiplexing signals "FREQ 1" and "FREQ 2" exhibit closed loop non-inverting gain of +2 each based upon identical  $330\Omega$  resistors in the gain setting positions of IC1 and IC2. The two multiplexing signals are combined at the input of IC3, which is the third LMH6639. This amplifier may be used as a unity gain buffer or may be used to set a particular gain for the circuit.




Figure 47. Switching between 5 and 10MHz

1k resistors are used to set an inverting gain of -1 for IC3 in the circuit of Figure 46. Figure 47 illustrates the waveforms produced. The upper trace shows the switching waveform used to switch between the 5MHz and 10MHz multiplex signals. The lower trace shows the output waveform consisting of 5MHz and 10MHz signals corresponding to the high or low state of the switching signal.



In the circuit of Figure 46, the outputs of IC1 and IC2 are tied together such that their output impedances are placed in parallel at the input of IC3. The output impedance of the disabled amplifier is high compared both to the output impedance of the active amplifier and the  $330\Omega$  gain setting resistors. The closed loop output resistance for the LMH6639 is around  $0.2\Omega$ . Thus the active state amplifier output impedance dominates the input node to IC3, while the disabled amplifier is assured of a high level of suppression of unwanted signals which might be present at the output.

## **SHUTDOWN OPERATION**

With  $\overline{SD}$  pin left floating, the device enters normal operation. However, since the  $\overline{SD}$  pin has high input impedance, it is best tied to V<sup>+</sup> for normal operation. This will avoid inadvertent shutdown due to capacitive pick-up from nearby nodes. LMH6639 will typically go into shutdown when  $\overline{SD}$  pin is more than 1.7V below V<sup>+</sup>, regardless of operating supplies.

The  $\overline{SD}$  pin can be driven by push-pull or open collector (open drain) output logic. Because the LMH6639's shutdown is referenced to V+, interfacing to the shutdown logic is rather simple, for both single and dual supply operation, with either form of logic used. Typical configurations are shown in Figure 48 and Figure 49 below for push-pull output:




Figure 48. Shutdown Interface (Single Supply)




Figure 49. Shutdown Interface (Dual Supplies)

Common voltages for logic gates are +5V or +3V. To ensure proper power on/off with these supplies, the logic should be able to swing to 3.4V and 1.4V minimum, respectively.

LMH6639's shutdown pin can also be easily controlled in applications where the analog and digital sections are operated at different supplies. Figure 50 shows a configuration where a logic output, SD, can turn the LMH6639 on and off, independent of what supplies are used for the analog and the digital sections:






Figure 50. Shutdown Interface (Single Supply, Open Collector Logic)

The LMH6639 has an internal pull-up resistor on  $\overline{SD}$  such that if left un-connected, the device will be in normal operation. Therefore, no pull-up resistor is needed on this pin. Another common application is where the transistor in Figure 50 above, would be internal to an open collector (open drain) logic gate; the basic connections will remain the same as shown.

### PCB LAYOUT CONSIDERATION AND COMPONENTS SELECTION

Care should be taken while placing components on a PCB. All standard rules should be followed especially the ones for high frequency and/ or high gain designs. Input and output pins should be separated to reduce crosstalk, especially under high gain conditions. A groundplane will be helpful to avoid oscillations. In addition, a ground plane can be used to create micro-strip transmission lines for matching purposes. Power supply, as well as shutdown pin de-coupling will reduce cross-talk and chances of oscillations.

Another important parameter in working with high speed amplifiers is the component values selection. Choosing high value resistances reduces the cut-off frequency because of the influence of parasitic capacitances. On the other hand choosing the resistor values too low could "load down" the nodes and will contribute to higher overall power dissipation. Keeping resistor values at several hundreds of ohms up to several  $k\Omega$  will offer good performance.

Texas Instruments suggests the following evaluation boards as a guide for high frequency layout and as an aid in device testing and characterization:

Device	Package	Evaluation Board PN
LMH6639MA	8-Pin SOIC	CLC730027
LMH6639MF	SOT-23-6	CLC730116



## **REVISION HISTORY**

Changes from Revision F (March 2013) to Revision G

Page





1-Nov-2013

### PACKAGING INFORMATION

Orderable Device	Status	Package Type	Package Drawing	Pins	Package Qty	Eco Plan	Lead/Ball Finish	MSL Peak Temp	Op Temp (°C)	Device Marking (4/5)	Samples
LMH6639MA	NRND	SOIC	D	8	95	TBD	Call TI	Call TI	-40 to 85	LMH66 39MA	
LMH6639MA/NOPB	ACTIVE	SOIC	D	8	95	Green (RoHS & no Sb/Br)	CU SN	Level-1-260C-UNLIM	-40 to 85	LMH66 39MA	Samples
LMH6639MAX/NOPB	ACTIVE	SOIC	D	8	2500	Green (RoHS & no Sb/Br)	CU SN	Level-1-260C-UNLIM	-40 to 85	LMH66 39MA	Samples
LMH6639MF	NRND	SOT-23	DBV	6	1000	TBD	Call TI	Call TI	-40 to 85	A81A	
LMH6639MF/NOPB	ACTIVE	SOT-23	DBV	6	1000	Green (RoHS & no Sb/Br)	CU SN	Level-1-260C-UNLIM	-40 to 85	A81A	Samples
LMH6639MFX/NOPB	ACTIVE	SOT-23	DBV	6	3000	Green (RoHS & no Sb/Br)	CU SN	Level-1-260C-UNLIM	-40 to 85	A81A	Samples

(1) The marketing status values are defined as follows:

ACTIVE: Product device recommended for new designs.

LIFEBUY: TI has announced that the device will be discontinued, and a lifetime-buy period is in effect.

NRND: Not recommended for new designs. Device is in production to support existing customers, but TI does not recommend using this part in a new design.

PREVIEW: Device has been announced but is not in production. Samples may or may not be available.

**OBSOLETE:** TI has discontinued the production of the device.

(2) Eco Plan - The planned eco-friendly classification: Pb-Free (RoHS), Pb-Free (RoHS Exempt), or Green (RoHS & no Sb/Br) - please check http://www.ti.com/productcontent for the latest availability information and additional product content details.

TBD: The Pb-Free/Green conversion plan has not been defined.

**Pb-Free (RoHS):** TI's terms "Lead-Free" or "Pb-Free" mean semiconductor products that are compatible with the current RoHS requirements for all 6 substances, including the requirement that lead not exceed 0.1% by weight in homogeneous materials. Where designed to be soldered at high temperatures, TI Pb-Free products are suitable for use in specified lead-free processes.

**Pb-Free (RoHS Exempt):** This component has a RoHS exemption for either 1) lead-based flip-chip solder bumps used between the die and package, or 2) lead-based die adhesive used between the die and leadframe. The component is otherwise considered Pb-Free (RoHS compatible) as defined above.

Green (RoHS & no Sb/Br): TI defines "Green" to mean Pb-Free (RoHS compatible), and free of Bromine (Br) and Antimony (Sb) based flame retardants (Br or Sb do not exceed 0.1% by weight in homogeneous material)

- (3) MSL, Peak Temp. The Moisture Sensitivity Level rating according to the JEDEC industry standard classifications, and peak solder temperature.
- (4) There may be additional marking, which relates to the logo, the lot trace code information, or the environmental category on the device.
- (5) Multiple Device Markings will be inside parentheses. Only one Device Marking contained in parentheses and separated by a "~" will appear on a device. If a line is indented then it is a continuation of the previous line and the two combined represent the entire Device Marking for that device.



# **PACKAGE OPTION ADDENDUM**

1-Nov-2013

(6) Lead/Ball Finish - Orderable Devices may have multiple material finish options. Finish options are separated by a vertical ruled line. Lead/Ball Finish values may wrap to two lines if the finish value exceeds the maximum column width.

**Important Information and Disclaimer:** The information provided on this page represents TI's knowledge and belief as of the date that it is provided. TI bases its knowledge and belief on information provided by third parties, and makes no representation or warranty as to the accuracy of such information. Efforts are underway to better integrate information from third parties. TI has taken and continues to take reasonable steps to provide representative and accurate information but may not have conducted destructive testing or chemical analysis on incoming materials and chemicals. TI and TI suppliers consider certain information to be proprietary, and thus CAS numbers and other limited information may not be available for release.

In no event shall TI's liability arising out of such information exceed the total purchase price of the TI part(s) at issue in this document sold by TI to Customer on an annual basis.

PACKAGE MATERIALS INFORMATION

www.ti.com 23-Sep-2013

## TAPE AND REEL INFORMATION





	Dimension designed to accommodate the component width
	Dimension designed to accommodate the component length
K0	Dimension designed to accommodate the component thickness
W	Overall width of the carrier tape
P1	Pitch between successive cavity centers

QUADRANT ASSIGNMENTS FOR PIN 1 ORIENTATION IN TAPE



### \*All dimensions are nominal

di dinensions die nominal												
Device	Package Type	Package Drawing		SPQ	Reel Diameter (mm)	Reel Width W1 (mm)	A0 (mm)	B0 (mm)	K0 (mm)	P1 (mm)	W (mm)	Pin1 Quadrant
LMH6639MAX/NOPB	SOIC	D	8	2500	330.0	12.4	6.5	5.4	2.0	8.0	12.0	Q1
LMH6639MF	SOT-23	DBV	6	1000	178.0	8.4	3.2	3.2	1.4	4.0	8.0	Q3
LMH6639MF/NOPB	SOT-23	DBV	6	1000	178.0	8.4	3.2	3.2	1.4	4.0	8.0	Q3
LMH6639MFX/NOPB	SOT-23	DBV	6	3000	178.0	8.4	3.2	3.2	1.4	4.0	8.0	Q3

www.ti.com 23-Sep-2013




\*All dimensions are nominal

7 iii dimensione dre nomina							
Device	Package Type	Package Drawing	Pins	SPQ	Length (mm)	Width (mm)	Height (mm)
LMH6639MAX/NOPB	SOIC	D	8	2500	367.0	367.0	35.0
LMH6639MF	SOT-23	DBV	6	1000	210.0	185.0	35.0
LMH6639MF/NOPB	SOT-23	DBV	6	1000	210.0	185.0	35.0
LMH6639MFX/NOPB	SOT-23	DBV	6	3000	210.0	185.0	35.0

# DBV (R-PDSO-G6)

# PLASTIC SMALL-OUTLINE PACKAGE



NOTES:

- A. All linear dimensions are in millimeters.
- B. This drawing is subject to change without notice.
- C. Body dimensions do not include mold flash or protrusion. Mold flash and protrusion shall not exceed 0.15 per side.
- D. Leads 1,2,3 may be wider than leads 4,5,6 for package orientation.
- Falls within JEDEC MO-178 Variation AB, except minimum lead width.



# D (R-PDSO-G8)

## PLASTIC SMALL OUTLINE



NOTES:

- A. All linear dimensions are in inches (millimeters).
- B. This drawing is subject to change without notice.
- Body length does not include mold flash, protrusions, or gate burrs. Mold flash, protrusions, or gate burrs shall not exceed 0.006 (0,15) each side.
- Body width does not include interlead flash. Interlead flash shall not exceed 0.017 (0,43) each side.
- E. Reference JEDEC MS-012 variation AA.



#### IMPORTANT NOTICE

Texas Instruments Incorporated and its subsidiaries (TI) reserve the right to make corrections, enhancements, improvements and other changes to its semiconductor products and services per JESD46, latest issue, and to discontinue any product or service per JESD48, latest issue. Buyers should obtain the latest relevant information before placing orders and should verify that such information is current and complete. All semiconductor products (also referred to herein as "components") are sold subject to TI's terms and conditions of sale supplied at the time of order acknowledgment.

TI warrants performance of its components to the specifications applicable at the time of sale, in accordance with the warranty in TI's terms and conditions of sale of semiconductor products. Testing and other quality control techniques are used to the extent TI deems necessary to support this warranty. Except where mandated by applicable law, testing of all parameters of each component is not necessarily performed.

TI assumes no liability for applications assistance or the design of Buyers' products. Buyers are responsible for their products and applications using TI components. To minimize the risks associated with Buyers' products and applications, Buyers should provide adequate design and operating safeguards.

TI does not warrant or represent that any license, either express or implied, is granted under any patent right, copyright, mask work right, or other intellectual property right relating to any combination, machine, or process in which TI components or services are used. Information published by TI regarding third-party products or services does not constitute a license to use such products or services or a warranty or endorsement thereof. Use of such information may require a license from a third party under the patents or other intellectual property of the third party, or a license from TI under the patents or other intellectual property of TI.

Reproduction of significant portions of TI information in TI data books or data sheets is permissible only if reproduction is without alteration and is accompanied by all associated warranties, conditions, limitations, and notices. TI is not responsible or liable for such altered documentation. Information of third parties may be subject to additional restrictions.

Resale of TI components or services with statements different from or beyond the parameters stated by TI for that component or service voids all express and any implied warranties for the associated TI component or service and is an unfair and deceptive business practice. TI is not responsible or liable for any such statements.

Buyer acknowledges and agrees that it is solely responsible for compliance with all legal, regulatory and safety-related requirements concerning its products, and any use of TI components in its applications, notwithstanding any applications-related information or support that may be provided by TI. Buyer represents and agrees that it has all the necessary expertise to create and implement safeguards which anticipate dangerous consequences of failures, monitor failures and their consequences, lessen the likelihood of failures that might cause harm and take appropriate remedial actions. Buyer will fully indemnify TI and its representatives against any damages arising out of the use of any TI components in safety-critical applications.

In some cases, TI components may be promoted specifically to facilitate safety-related applications. With such components, TI's goal is to help enable customers to design and create their own end-product solutions that meet applicable functional safety standards and requirements. Nonetheless, such components are subject to these terms.

No TI components are authorized for use in FDA Class III (or similar life-critical medical equipment) unless authorized officers of the parties have executed a special agreement specifically governing such use.

Only those TI components which TI has specifically designated as military grade or "enhanced plastic" are designed and intended for use in military/aerospace applications or environments. Buyer acknowledges and agrees that any military or aerospace use of TI components which have *not* been so designated is solely at the Buyer's risk, and that Buyer is solely responsible for compliance with all legal and regulatory requirements in connection with such use.

TI has specifically designated certain components as meeting ISO/TS16949 requirements, mainly for automotive use. In any case of use of non-designated products, TI will not be responsible for any failure to meet ISO/TS16949.

### Products Applications

Audio www.ti.com/audio Automotive and Transportation www.ti.com/automotive Communications and Telecom Amplifiers amplifier.ti.com www.ti.com/communications **Data Converters** dataconverter.ti.com Computers and Peripherals www.ti.com/computers **DLP® Products** www.dlp.com Consumer Electronics www.ti.com/consumer-apps

DSP **Energy and Lighting** dsp.ti.com www.ti.com/energy Clocks and Timers www.ti.com/clocks Industrial www.ti.com/industrial Interface interface.ti.com Medical www.ti.com/medical logic.ti.com Logic Security www.ti.com/security

Power Mgmt <u>power.ti.com</u> Space, Avionics and Defense <u>www.ti.com/space-avionics-defense</u>

Microcontrollers microcontroller.ti.com Video and Imaging www.ti.com/video

RFID www.ti-rfid.com

OMAP Applications Processors <u>www.ti.com/omap</u> TI E2E Community <u>e2e.ti.com</u>

Wireless Connectivity <u>www.ti.com/wirelessconnectivity</u>